7	Pro ing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	234.60		
8	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	586.50		
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	105.57		

Number of Corrections: Nil

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

DTS Approved

29/10/14

4 ಪಸ್ತು ಆತಯಾನ ಪುಸ್ತಂಯಲ್ಲಿ ಇದೆ ೧

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು, 29/10
ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ,
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು.

ಪ್ರತಿಯನ್ನು ಮಾಹಿತಿಗಾಗಿ ಸಲ್ಲಿಸಿದೆ:-

1 ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು, (ಶೆಟ್ಟಿಹಳ್ಳಿ, ಟಿ.ದಾಸರಹಳ್ಳಿ, ಪೀಣ್ಯ ಕೈಗಾರಿಕಾ ಪ್ರದೇಶ ಮತ್ತು ಹೆಗ್ಗನಹಳ್ಳಿ) ಉಪ ವಿಭಾಗ, ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ, ದಾಸರಹಳ್ಳಿ ವಲಯ ಬೆಂಗಳೂರು. ಮೂಲ ಅಂದಾಜು ಪಟ್ಟಿಯೊಂದಿಗೆ ಮುಂದಿನ ಕ್ರಮಕ್ಕಾಗಿ.

2 ಸಹಾಯಕ ಹಣಕಾಸು ನಿಯಂತ್ರಕರು, ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ, ಬೆಂಗಳೂರು.

3 ಕಛೇರಿ ಪ್ರತಿ.